

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21231-00-00
Spot: CNENENW Sec/Twnshp/Rge: 4-12S-22W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: EHR FARMS Well Number: 1
County: TREGO Total Vertical Depth: 4105 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: PO BOX 780428
WICHITA, KS 67278

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 209 225 SX CMT
Production: Size 4.5 feet: 4095 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/15/2002 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 300# hulls.
D.V. Tool at 1885' and set with 425 sxs cement.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/15/2002 10:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded off bottom to 3950' and topped with 4 sxs cement using a dump bailer.
Perforated casing at 2450' - tied onto 4 1/2" and pumped 200 sxs cement with 300# hulls.
Max. P.S.I. 500#. S.I.P. 100#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Jay Pfeifer
RECEIVED
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

JAN 17 2002
01-17-2002
CONSERVATION DIVISION

INVOICED
DATE Jan 18-02
2002061275

Form CP-2/3

JAN 15 2002

ZENITH DRILLING CORPORATION

505 FOURTH FINANCIAL CENTER

WICHITA, KS 67202

#1 E.H.R. FARMS

4-12-22W
NE NE NW

CONTR DNB DRILLING, INC.

CTY TREGO

GEOL _____

FIELD SHAW CREEK

EXT (1/4 S)

ELV 2407 KB SPD 3/22/83

CARD ISSUED


7/7/83

IP P 25 BOPD, NW

2404 GL

API 15-195-21,231

MARM 4012-4032



LOG Tops Depth/Datum

ANH	1849+ 558
HEEB	3644-1237
LANS	3680-1273
MARM	4005-1598
RTD	4105-1698

8 5/8 " 209/225SX; 4 1/2 " 4095/125SX **EA**

DST (1) 3746-64 (LKC) / 30-30-60-60, REC 80' OCM, 120' MCO,
SIP 721-773#, FP 21-21 / 85-85#

DST (2) 3752-76 (LKC) / 30-30-60-60, REC 600' SW, SIP 690-
690#, FP 21-106 / 213-223#

DST (3) 4014-54 (MARM) / 30-60-60-90, REC 180' VHOCM, SIP
1160-1129#, FP 21-21 / 85-85#

MICT - CO, PF (MARM) 4012-32 W/2-SPF, AC 1500G (15% MCA),
FRAC 1500 BBLS 2% KCLW & 40,000# SD, SWB DWN, GSO,
POP, P 25 BOPD, NW (GR 35%), 6/9/83

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS