

4-041614

9-8

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-195-21291-00-00

NE NE SE /4 SEC. 04, 12 S, 22 W
2310 feet from S section line
330 feet from E section line

Operator license# 4767 Lease EHR Farm well # 1

Operator: Ritchie Exploration, Inc. County Trego

Address: 125 N. Market Suite #100 Wichita, Kansas 67202
Well total depth 4120 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 244 feet w/165 sxs.

133,90

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 8 Month: September Year: 94

Plugging proposal received from: Pete Fiourinni

Company: Ritchie Exploration, Inc. Phone:

Were: 4 1/2" casing set @ 4119' w/175 sxs. cmt. Perf. @ 3671' - 4032'.
D.V. Anhy. @ 1864' w/450 sxs. T.O.F. @ 1800'.

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1994
CONSERVATION DIVISION
WICHITA, KANSAS

Ordered 225 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 400# hulls

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:00P.M. Day: 8, Month: September, Year: 94

Actual plugging report: Rig up cementers to squeeze 4 1/2" casing with
225 sxs. cement plus 400# hulls in cement. Pumped same. Max. P.S.I.
400#. 8 5/8" S.P. Pressured-up to 500# cement at surface.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: GL

I did [X] did not [] observe the plugging.

Dennis L. Hamel

INVOICED
DATE SEP 27 1994
INV. NO. 41275

(agent)
Form CP-2/3