

To: **6 031512**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-15
API NUMBER **15-195-21-481-00-00**
NW, SEC. **3**, T **12** S, R **22** W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Operator: Ritchie Exp Inc.

Name & Address 125 N. Market Suite 1000

Wichita, Ks. 67202-1275

440 feet from S section line

4840 feet from E section line

Lease Name WHR Well # 2

County Trego **133.77**

Well Total Depth 4116 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 247

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement Co. License Number _____

Address Russell, Ks.

Company to plug at: Hour: AM Day: 15 Month: Mar Year: 19 91

Plugging proposal received from Pete

(company name) Ritchie (phone) _____

were: 8 5/8 set at 247 w/200. 4 1/2 set at 4108 w/175 sks. PBTD 4064 w/
DV tool at 1843 cwc 475 sks. Perf 4018 - 40. Order 225 sks 65/35 poz
10% gel. 500 lbs. hulls. Allied Cement Co. Rush water truck.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:10AM Day: 15 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Sq 4 1/2 w/225 sks cement blend w/500 lbs. hulls mixed in to
max psi 1100 lb. Close in psi 900 lbs. Tested 8 5/8 w/two strokes of
pump, pressure hit 500 lbs. Released cement at surf. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
04-04-1991
APR 04 1991

Remarks: Anhy 1832 - 78 Elev. 2391 GL

CONSERVATION DIVISION
Wichita, Kansas

INVOICED (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 4-11-91

INV. NO. 31497

J.S.

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow