

236 R

4-17

6 031348

API NUMBER 15- 195-21,327-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW NW, SEC. 3, T 12 S, R 22 W/E
4950 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name W. H. R. Well # 1

Operator: Ritchie Exp

County Trego 133.41

Name & Address 125 N. Market #1000

Well Total Depth 4105 feet

Wichita, Ks. 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 227

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 17 Month: April Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone)

were: 8 5/8 set at 227 w/140 sks cwc. 4 1/2 set at 4104 w/175 sks. Perf 4002 - 22. Order

225 sks 65/35 poz 10% gel 2% dicel 500# hulls. Allied Cement Co. Wellbrock water trucks.

2 staged 6 shots at 2600 to 1000 include anhydrite and base of dakota;no stretch.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:00PM Day: 17 Month: April Year: 19 90

ACTUAL PLUGGING REPORT sq 4 1/2 casing w/130 sks cement blend to max psi

800# close in psi 200#. Sq backside 8 5/8 annulus w/60 sks to max psi 600#. Close in

200#. Plug complete.

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-9-90

INV. NO. 28082

RECEIVED
MAY 03 1990
G.B.S.

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow