

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03067-00-00
Spot: NENWNE Sec/Twnshp/Rge: 12-10S-23W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: IRWIN Well Number: 3
County: GRAHAM RTKCC Total Vertical Depth: 4122 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

Production Casing Size: 5.5 feet: 4121
Surface Casing Size: 8.625 feet: 165

\$133.91

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/15/2003 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC
Proposal Rcvd. from: ALLEN BANGERT Company: GLM COMPANY Phone: (785) 483-1676

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 10% gel - 700# hulls - 11 sxs gel.
Emergency plug with rig over hole.
Perfs at 3678' - 4091'. Holes in casing at top of cement and 300'.

Plugging Proposal Received By: CASE MORRIS
Date/Time Plugging Completed: 05/15/2003 1:00 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)
KCC Agent: PAT STAAB

Actual Plugging Report:

Perforated a two shot hole at 1100' - 1975' - 2575'.
Express Well Service RIH with tubing to 3600' - pumped 100 sxs cement with 300# hulls.
Pulled tubing to 3006' - pumped 11 sxs gel with 200# hulls.
Pulled tubing to 2515' - pumped 75 sxs 60/40 pozmix with 100# hulls.
Pulled tubing to 1152' - pumped 80 sxs 60/40 pozmix with 100# hulls to circulate cement.
Pulled tubing and topped with 50 sxs to fill casing to surface.
Tied onto backside. Max. P.S.I. 500#. S.I.P. 500#.

RECEIVED
MAY 21 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #14652.

Plugged through: TBG

District: 04

Signed *Pat Staab*

(TECHNICIAN)

INVOICE

DATE 5-22-03
INV. NO. 200306156-3

Form CP-2/3

MAY 15 2003

HEATHMAN-SEELIGSON

#3

ERWIN

12-10-23W

NE NW NE

GRAHAM

County

Contr.

E 2414

RB

Comm.

8-6-55

Comp. 9-16-55

IP

434 BOPD

Tops	Depth	Datum
ANH	1951	463
HEEB	3646	-1232
TOR	3668	-1254
LANS	3682	-1268
B/KC	3914	-1500
MARM CH	3994	-1580
MARM SND	4083	-1669
TD	4122	-1708

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Casing

8" 165

5" 4121 $\frac{1}{2}$

DST 3684-3705/2 HR, 60' H OCM, BHP 1020#
 DST 3713-29/2 HR, 215' GAS, 85' H OCM
 BHP 650#: DST 3736-63/2 HR, 300' O & GCM
 BHP 1030#: DST 3813-38/2 HR, 930' O &
 GC SW, BHP 930#: DST 3839-54/2 HR,
 1200' GAS, 180' MDY OIL, BHP 790#
 DST 3859-71/2 HR, 200' OIL, BHP 570#
 DST 3881-94/2 HR, 290' SW, BHP 1090#
 DST 4070-98/2 HR, 330' OIL, 120' V H
 OCM, BHP 730#

LAW SE POOL

CO 4106: 60/3852-62

ACID 1000: SWB 15-16

BOPH, NO WTR:

