

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-03066-00-00  
Spot: CSWNWNE Sec/Twnshp/Rge: 12-10S-23W  
4290 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: <sup>KTCC</sup>ERWIN Well Number: 2  
County: GRAHAM Total Vertical Depth: 4098 feet

Operator License No.: 31901  
Op Name: RED MOUNTAIN OIL LLC  
Address: PO BOX 46  
GOLDEN, CO 80402

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 187  
Production: Size 5.5 feet: 4097  
Liner: Size feet:

\$133.19

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/17/2001 10:00 AM

Plug Co. License No.: 31901 Plug Co. Name: RED MOUNTAIN OIL LLC

Proposal Rcvd. from: STEVE THOMASON Company: THOMASON OIL, INC. Phone: (785) 623-1174

Proposed 5 1/2" casing set at 4097'.  
Plugging Perforations: 3678' - 4096'. P.B.T.D. 3170' - Drilling mud.  
Method: Squeeze records only Cedar Hills on October 31, 1965 with 100 sxs.  
Perforate salt at 2450'. Anhy at 2020'. Dakota at 1100'.  
Run tubing in 2500'+. Squeeze to capacity.  
Ordered 375 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 05/17/2001 4:00 PM

KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Fisher Well Service rigged up over hole.  
ELI perforated at 2450' - 2020' - 1100'.  
PBTD 3170'. Soft drilling mud. Fluid level at 300'.  
Ran tubing to 2520'. Allied pumped 150 sxs with 200# hulls.  
Pulled tubing to 1953'. Pumped 100 sxs with 150# hulls.  
Pulled tubing to 1100' and pumped 70 sxs with 150# hulls, cement circulated.  
P.T.O.H. Squeezed 35 sxs.  
Max. P.S.I. 500#. S.I.P. 200#.

**INVOICED**

DATE 5-29-01

INV. NO. 2001061852

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 22 2001

CONSERVATION DIVISION

Remarks: LEASE ALSO KNOWN AS LAW UNIT SE #2.

Plugged through: TBG

Bob

District: 04

Signed

Richard Williams

(TECHNICIAN)

HEATHMAN-SEELIGSON

#2

ERWIN

12-10-23W  
SW NW NE

Contr.

GRAHAM

County

E. 2121 RBComm. 6-10-55 Comp. 7-22-55 IP 516 BOPD

Tops	Depth	Datum
ANH	1960	461
TOP	3475	-1054
HEEB	3651	-1230
TOR	3671	-1250
LANS	3687	-1266
B/KC	3915	-1494
MARM SND	4091	-1670
ID	4098	-1677

Casing  
 8" 187 DST 3689-3710/2 HR, 2700' GAS, 1010'  
 5" 4097 FR OIL, BHP 1080#: DST 3716-32/2 HR,  
 960' GAS, 120' OIL, 60' H O & GCM, BHP 1240#:  
 DST 3750-96/2 HR, 180' GAS, 930' H O & GC  
 MDY WTR, BHP 1180#: DST 3816-36/1 HR, 10' MUD  
 BHP 530#: DST 3840-56/2 HR, 330' G, 90' OCM  
 BHP 920#: DST 3862-78/2 HR, 1120' O, BHP 200#  
 DST 3883-96/2 HR, 2640' SW, BHP 1250#: DST  
 4023-98/2 HR, 300' MD OIL, 510' H OCM, 820#  
 PERF 32/4088-96: SWB 38 GOPH/4 HR: FRAC;  
 SWB 6 BOPH/1 HR, NW: PB 3925: 18/3828-85:  
 SWB 10 GOPH: PB 3878: 48/3862-74: SWB 2 1/2  
 BOPH, SSW: ACID 2000: SWB 15 BFPH, 35% WTR  
 SQZ: REPERF 3862-68  
 ACID 500: SWB 15 1/2 BOPH/  
 4 1/2 HR, NW

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS