

To: 6 031060
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Operator: Petroleum Inc.
Name & Address: Box 1447
Great Bend, Ks. 67530

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement License Number _____

Address Plainville, Ks.

Company to plug at: Hour: AM Day: 19 Month: April Year: 19 88

Plugging proposal received from Evert Jones

(company name) Pet. Inc. (phone) _____

were: 8 5/8" set @ 247' w/ 150 sx, 5 1/2" set @ 3974' w/ 150 sx. PBTB 3927'. Perfs 3837-3916',

2 shots @ Anhydrite 1960-61', 2 shots @ Dakota - 50' in Kiowa Shale. Order 250 sx ATL cement blend and 5 sx hulls. Allied Cmt. Co. and Sundowner Water Trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour 10:30AM Day: 19 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 5 1/2" w/ 50 sx cement followed w/ 150 sx cement w/ 4 sx hulls mixed in. Max pressure psi 900#. Close in psi 500#. Squeeze annulus w/ 50 sx cement w/ 1 sx hulls mixed in. Maximum psi 700#. Close in 500#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

07-06-88
JUL 6 1988

Remarks: _____

(If additional description is necessary, use BACK of this form.)

INVOICED
I did observe this plugging.

DATE 7-8-88
INV. NO. 21237

Signed Carl Goodrow
Carl Goodrow (TECHNICIAN)