

6 062038

12-18

API NUMBER 13-195-20920-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE , SEC. 5, T 12 S, R 22 W

2310 feet from S section line

1650 feet from E section line

Lease Name Rinker Well # 1

County Trego 134.42

Well Total Depth 4136 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 256

TECHNICIAN'S PLUGGING REPORT

Operator License # 4419

Operator: Bear Petroleum

Name & Address Box 438

Haysville, Ks. 67060

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Paramount Enterprises Inc. License Number 3763

Address 2905 Barclay Drive Hays, Ks. 67601

Company to plug at: Hour: 9:00AM Day: 18 Month: Dec Year: 19 89

Plugging proposal received from Ronald Geist

(company name) Paramount Enterprises Inc. (phone) 913-628-1099

were: Order 300 sks 60/40 poz 8% gel 5 sks hulls.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:00 PM Day: 18 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT 8 5/8" set at 256' w/245 sks. 4 1/2" set at 4134' w/150 sks.

Top perf at 4089'. Plugged bottom w/sand and 4 sks cement to 4050'. Shot pipe one

time and recovered 2550'. Pumped in 8 5/8" 25 sks cement followed w/5 sks hulls in

275 sks cement w/700 psi.

RECEIVED
STATE CORPORATION COMMISSION

JAN 17 1990

Remarks: By Allied. Ran line to 1700'

INVOICED

Additional description is necessary, use BACK of this form. CONSERVATION DIVISION
Wichita, Kansas

(did xxxxxxxx) observe this plugging.

DATE JAN 24 1990

Signed Gilbert G. Scheck
Gilbert G. (TECHNICIAN)

INV. NO. 27102