

8-13-88

6 070710

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 195-21,986-00-00  
NW NE NW SEC. 7, T 12 S, R 22 W/E

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5418

RECEIVED  
STATE CORPORATION COMMISSION  
08-30-1988  
AUG 30 1988

4950 feet from S section line  
3630 feet from E section line

Operator: Allen Drilling Co.  
Name & Address: Box 1389  
Great Bend, Ks. 67530  
Doug Hoisington

Lease Name Newcomer Well # 1-7  
County Trego 135.20

Well Total Depth 4160 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated Rig Tag #154

Plugging Contractor Allen Drilling Company License Number

Address Box 1389 Great Bend, Ks. 67530

Company to plug at: Hour: AM Day: 13 Month: Aug Year: 19 88

Plugging proposal received from Craig Christopher

(company name) Allen Drilling Inc. (phone)

were: 8 5/8" -304' S.P. cwc w/175 sks 60/40 Poz 2% Gel 3% Ca Cl. By Halco.  
Arbuckle 4103'; Elv. 2409'; No circulation problems, Mud condition 47 vis; 9.1 lb. weight;  
water loss 8; Proposal 225 sks 60/40 Poz 6% Gel 3% Ca Cl and 8 5/8" plug. Spot with drill  
stem, circulate, heavy mud between all plugs. 25 sks at 4046'; 25 sks at 1840'; 100 sks  
w/1 sk F.C. at 1000'; 50 sks at 350'; Halls plug at 40' w/10 sks cement. 15 sks in rathole.

(circulate) Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:00PM Day: 13 Month: Aug Year: 19 88

ACTUAL PLUGGING REPORT Ordered 225 sks 60/40 Poz 6% Gel 3% Ca Cl and 8 5/8" plug.

Spotted with drill stem, circulated, mud between all plugs. 1st plug at 4046' w/25 sks cement;  
2nd plug at 1840' w/25 sks cement; 3rd plug at 1000' w/100 sks cement w/1 sk F.C. added;  
4th plug at 350' w/50 sks cement; 5th plug Halls, plug at 40' w/10 sks cement; 15 sks in rat-  
hole. (circulate) Cemented by Halliburton Cement Co.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED  
I (did/did not) observe this plugging.

DATE 8-31-88

INV. NO. 22052

Signed Marion J. Schmidt (TECHNICIAN)  
Marion J. Schmidt