

8-25

176
R

6-050078

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-195-22,092-00-00

SE NW SE /4 SEC. 6 , 12 S , 22 W
1650 feet from S section line
1650 feet from E section line

Operator license# 5663 Lease Rinker well # 1

Operator: Hess Oil Company County Trego

Address: 412 E. Douglas #1 Well total depth 2065 feet
Wichita, Kansas 67202 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 218 feet

67.11

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Mallard JV License# 4958

Address: As above

Company to plug at: Hour: 4:30 pm Day: 25 Month: August Year: 91

Plugging proposal received from: Arnie Hess

Company: Hess Oil Co. phone:

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 1840 feet with 20 sacks Rat hole: 15 sacks

2nd plug @ 1015 feet " 100 " Mousehole: 10 sacks

3rd plug @ 270 feet " 40 "

4th plug @ 40 feet " wiper plug & 10 sx

RECEIVED
STATE CORPORATION COMMISSION

OCT 01 1991

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Bruce D. Basye

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 4:30 pm, Day: 25, Month: August, Year: 1991

Actual plugging report: Hole reported plugged as above.

Order 195 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2415 GL, Anhydrite depth: 1847 - 1859 feet

Did not penetrate Arbuckle, cemented by Allied

I did not observe the plugging. Bruce D. Basye

DATE 10-4-91
INV. NO. 33247

G. S.

Bruce D. Basye