

4-031784

11-4

95
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-195-21,057-0000

SE SE NE /4 SEC. 05, 12 S, 22 W
2970 feet from S section line
330 feet from E section line

Operator license# 4419 Lease Babb well # 1

Operator: Bear Petroleum, Inc. County Trego

135.20

Address: Box 438 Well total depth 4160 feet
Haysville, Kasnas 67060 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 220 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Gressel License# 2514

Address: Burton, Kansas

Company to plug at: Hour: P.M. Day: 4 Month: November Year: 92

Plugging proposal received from: Dick Schremmer

Company: Bear Petroleum, Inc. Phone: _____

Were: Order 275 sx. 65/35 pozmix - 10% gel. - 500# hulls.
Allied Cementing.
Casing open to perms.
Pulled rods & tubing.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 5:30P.M., Day: 4, Month: November, Year: 92

Actual plugging report: 8 5/8" set @ 220' w/120 sx. cwc. 4 1/2" set @
4159' w/150 sx. Perf. 4016' - 4031'. P.B.T.D. 4025'. Shots @ 1800' -
1100'. Squeezed 4 1/2" w/200 sx. cement blend w/400# hulls.
Mixed in to Max. P.S.I. 200#. Close in P.S.I. 200#. Squeezed 8 5/8"
w/75 sx. cement blend w/100# hulls. Mixed in to 100#. Close in P.S.I.100#.
Plug complete.

Remarks: _____
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL _____

RECEIVED
STATE CORPORATION COMMISSION
11-23-1992
NOV 23 1992

I did did not observe the plugging. Carl Goodrow (agent)

INVOICED
DATE 11-24-92
ENT. NO. 36919