

To: 6 031574 15-065-01880-0004-19
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A

211 R

SW SE SW, SEC. 16, T 10 S, R 23 (W) E

330 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30241

Lease Name Diebolt LKC Well # Unit 2--5

Operator: Geneva Resources, Inc.

County Graham 125.77

Name &

Address 50 California Street

Well Total Depth 3870' feet

Suite 930

Conductor Pipe: Size feet

San Francisco, California

Surface Casing: Size 8 5/8 feet 278'

94111

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Company License Number

Address Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 19 Month: 7 Year: 19 91

Plugging proposal received from Gerald

(company name) Geneva Resources, Inc. (phone)

were: 8 5/8 set @ 278' w/175 sx. cwc. 5 1/2 set @ 3869' w/175 sx. PBTD 3791' - 3689' - 3788'.

Order 350 sx. 65/35 doz. 10% gel. 500# hulls. Allied Cement Company. Express

Well Service. Wellbrock Water Trucks. Shot holes @ 1925' and 1100'. Hole open to

any. Junk in bottom of hole.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4:20 P.M. Day: 19 Month: 7 Year: 19 91

ACTUAL PLUGGING REPORT Ran tubing to 1800' circulated cement out 5 1/2" and out 8 5/8.

Closed in 8 5/8, laid down tubing. Squeezed 5 1/2 and 8 5/8 w/total of 350 sx.

cement blend w/500# hulls. Mixed in to max. P.S.I. 800#. Close in P.S.I. 500#.

Plug complete

RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1991

Remarks:

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 8-28-91

INV. NO. 37800

Signed Carl Goodrow (TECHNICIAN)