

6 031364

5-14

API NUMBER 15-065-01877-0002

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW, SEC. 16, T 10 S, R 23 XXX

1980 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30241

Lease Name Diebolt Unit Well # 2-2

Operator: Geneva Resources Inc.

County Graham 126.75

Name:

Well Total Depth 3900 feet

Address 50 California St. Suite 930

Conductor Pipe: Size feet

San Francisco, California 94111

Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Express Well Service License Number 2288

Address Victoria, Ks.

Company to plug at: Hour: PM Day: 14 Month: May Year: 19 90

Plugging proposal received from Gerald Riedel

(company name) Geneva (phone)

were: 8 5/8 set at 278 w/175 sks. 5 1/2 set at 3899 w/175 sks. PBTB 3864.

Stage collar set at 3339. Perfs 3797 - 3824. Perforated at 1925 and 1100'. Order 250

sks 65/35 poz 10% gel 500# hulls. Halliburton Cement Co. Wellbrock Water Trucks.

Plugging Proposal Received by Carl
(TECHNICIAN)Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 3:45PM Day: 14 Month: May Year: 19 90

ACTUAL PLUGGING REPORT Ran tubing to 2198. Mixed and pumped cmt blend through

tubing to circ w/190 sks. Layed down tubing sq 5 1/2 casing w/total of 220 sks. To max psi 300#.

Close in psi 150#. Sq 8 5/8 w/30 sks to max psi 300#. Close in psi 150#. Plug complete.

Remarks:

RECEIVED

STATE CORPORATION COMMISSION

additional description is necessary, use BACK of this form.)

(did not observe this plugging.)

CONSERVATION DIVISION
Wichita, Kansas

Signed

Carl Goodrow
(TECHNICIAN)

Carl Goodrow

FORM CP-2/3
Rev. 01-84

INVOICED 30 1990

DATE

6-5-90

INV. NO.

28304

05-30-90

5-14