

10-15
6-031606 15-065-01876-00009 ²⁶¹ R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- -

SW SW SW /4 SEC. 16, 10 S, 23 W
330 feet from S section line
4950 feet from E section line

Operator license# 30241

Lease Diebolt LKC Unit well # 2-1

Operator: Geneva Resources, Inc.

County Graham

Address: 50 California Street
Suite 930
San Francisco, CA 94111

Well total depth 4023 feet ^{1,30.74}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 278 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 15 Month: October Year: 91

Plugging proposal received from: Gerald Riedel

Company: Geneva Resources, Inc. Phone:

Were: 8 5/8" set @ 278' w/165 sx. cwc. 5 1/2" set @ 4023' w/175 sx.
PBTD 3990'. Perf. 3680' - 3830'. Stage collar @ 3346' w/ok gel.
Circulate to surface with 100 sx. cement blend to 2000# P.S.I.
Squeeze leak @ 1904' w/200 sx. Shots @ 1925 - 1100'.

Hole open to perf. and would take fluid.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 12:45A.M., Day: 15, Month: October, Year: 91

Actual plugging report: Squeezed 5 1/2" w/250 sx. cement blend w/400#
hulls mixed in to max. P.S.I. 500#. Close in P.S.I. 300#. Squeezed
8 5/8" w/100 sx. cement blend w/100# hulls to max P.S.I. 300#.
Close in P.S.I. 150#. Plug complete.

STATE CORPORATION COMMISSION

NOV 4 1991

Remarks:
CONSERVATION DIVISION
Wichita, Kansas

I did / did not observe the plugging. Carl Goodrow

INVOICED
DATE 11-15-91
INV. NO. 33741

G.S.

(agent)
Form CP-2/3