

6 030797

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5302

Operator: DR WELL OPERATORS INC.
Name & Address: 7585 W. ARKANSAS, STE. B
LAKEWOOD, COLORADO
80226

API NUMBER 15-195-21, 252-00-00
C N E N W SEC. 10, T. 12 S, R. 22 (W) E
4950 feet from S section line
3300 feet from E section line
Lease Name GRECIAN Well # 1

County TREGO 134.88
Well Total Depth 4150 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 212

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B-J TITAN License Number _____
Address HAYS KANSAS

Company to plug at: Hour: AM Day: 10 Month: 10 Year: 19 86

Plugging proposal received from HERMAN FELLHOUTER
(company name) DR WELL OPER. INC. (phone) _____

were: 8 5/8 SET @ 212 w/100sx 4 1/2 SET @ 4150 w/100sx. PORT COLLAR
@ 1018' w/200sx. Dropped - PBD 4110 PERF. 3998-4027, 4029-30
ORDER 250 sx. ECONOLITE 65/35002 10% GEL 2% DICEL 5sx. HULLS.
B-J TITAN CMT. CO. SUNDOWNER WATER TRUCK.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30AM Day: 10 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT TIE ON TO 8 5/8 - 4 1/2 ANNULUS MIX. & PUMP 20 bbl's
CEMENT SLURRY (40sx. CMT. MIX) TO PRESSURE. MAX. PSI 300# CLOSE IN 150#
TIE ON TO 4 1/2" CSG. MIX. & PUMP 25 bbl's CEMENT SLURRY (50sx. CMT. MIX)
w/ 4sx. HULLS BEHIND. THEN FOLLOWED w/160sx. CMT. MIX. @ 800# PUMP
PRESSURE TO END MAX. PSI OF 1200# CLOSE IN @ 900#
PLUG COMPLETE

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

(All interested parties) observe this plugging.

DATE 10-24-86

INV. NO. 15238
10-10

Signed Carl Goodrow
(TECHNICIAN)
OCT 24 1986
10-24-1986