

4-031928

5-23

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-195-20,716-00-00

NE SE /4 SEC. 10, 12 S, 22 W  
1980 feet from S section line  
660 feet from E section line

AKA B Malsam

Operator license# 4767

Lease Malsam "p" well # 1

Operator: Ritchie Exploration, Inc.

County Trego

Address: 125 N. Market  
Suite #1000  
Wichita, Kansas 67202

Well total depth 4115 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 205 feet

133.73

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: A.M. Day: 23 Month: May Year: 94

Plugging proposal received from: Richard

Company: Kelso Casing Pulling, Inc. Phone:           

Were: Order 200 sxs. 60/40 pozmix - 10% gel - 500# hulls  
Order sand and common cement.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 4:30 P.M., Day: 23, Month: May, Year: 94

Actual plugging report: 8 5/8" set @ 205' w/150 sxs. 4 1/2" set @ 4117'  
w/200 sxs. Prod. Perfs 3978' - 4012'. Sand back to 3920' w/4 sxs.  
common cement on sand with bailer. Shot at 2600' tight shot and  
recovered 2223' of 4 1/2". Mix and pumped 60 sxs. cement blend with 300#  
hulls to 2500' - pulled casing to 1700'. Pumped 55 sxs. cement blend  
slurry surface to 1700' with 500# P.S.I. Pulled casing to 200' circulated  
40 sxs. with 200# hulls - cement blend slurry to surface - pulled casing  
Cellar remained full of cement. Used total 155 sxs. cement with 500#  
hulls. Plug complete.

Remarks: Condition of casing(in hole): GOOD X BAD     Any plug: YES X NO      
Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:     GL    

I did [ X ] / did not [     ] observe the plugging. Carl Goodrow

DATE 6-7-94  
INV. NO. 40548

(agent)  
Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 03 1994  
06-03-1994  
CONSERVATION DIVISION  
Wichita, Kansas