

10-17

6 031440

API NUMBER 15-065-03075-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE SE SE , SEC. 17 , T 10 S, R 23

TECHNICIAN'S PLUGGING REPORT

Operator License # 30241

990 feet from S section line

330 feet from E section line

Operator: Geneva Resources Inc.  
Name & Address: 50 California St. Suite 930  
San Francisco, Ca. 94111

Lease Name Diebolt Unit Well # 1-3

County Graham 126.42

Well Total Depth 3890 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Services License Number

Address Hays, Ks.

Company to plug at: Hour: PM Day: 17 Month: Oct. Year: 19 90

Plugging proposal received from Gerald Riedel

(company name) Geneva (phone)

were: 8 5/8 set at 290 w/250 sks. cwc 5 1/2 set at 3899 w/150 sks.

D.V. tool 1933. Possibly circ. w/Cempac. Shot holes at 1925. Anhy and 1100 Kiowa  
Order 300 sks 65/35 poz 10% gel 500 lbs. hulls. Halliburton Cement Co. Sally's  
Water Trucks. Rig 757 Express Well Service. Hole open by wireline.

Plugging Proposal Received by Carl (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 6:17PM Day: 17 Month: Oct. Year: 19 90

ACTUAL PLUGGING REPORT ran tubing to 2000. Mix and pump thru tubing  
100 sks cement blend w/300 lbs. hulls mixed in, laid down 1000 of tubing. Mix and  
pump 200 sks to circ. Laid down tubing. Sq 5 1/2 w/total of 200 sks to max psi 400 lbs.  
Close in psi 400. Sq annulus w/100 sks. to max psi 300 lbs. Close in psi 200 lbs. Plug  
Complete.

RECEIVED STATE CORPORATION COMMISSION

NOV 8 1990

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-13-90 INV. NO. 29947

Signed Carl Goodrow (TECHNICIAN) Carl Goodrow