

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 10 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-195-20239-00-00

Operator's Full Name Black Petroleum, Incorporated,

Complete Address 445 O. W. Garvey Building, Wichita, Kansas.

Lease Name Babb Well No. 1

Location App.-CW/2-NW-NE Sec. 9 Twp. 12 Rge. (E) (W) 22

County Trego Total Depth 4108'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Shields Drilling Company, Incorporated,

Address Shields Building, Russell, Kansas. License No.       

Operation Completed: Hour 11:00 PM Day 8 Month 1 Year 1973

The above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 675'. (LANDOWNER REQUESTED WELL BE LEFT OPEN FOR FRESH  
WATER WELL).

Circulated hole with heavy mud. Pulled DP to 900' and displaced 120 Cu. Ft. cement  
thru DP from 900' to 550'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP to 185' and circulated hole with clear water.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dickals  
Well Plugging Supervisor

INVOICED

DATE 1/11/73

INV. NO. 6841-W