

15-065-20110-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
AUG 1 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
08-01-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Incorporated.

Complete Address P. O. Box #922, Great Bend, Kansas.

Lease Name Dietz Well No. 1

Location 2640' FNL & 2310' FNL of Sec. 17 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3940'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling Company, Incorporated.

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 1:30 PM Day 30 Month 7 Year 1969

The above well was plugged as follows:

208'--8 5/8" Surface casing, cement circulated with 150 Sx.

3939'--4 1/2" Production casing cemented on bottom with 250 Sx. Packer set @ 3904'. Top perforations from 3866' to 3872'.

Sanded well back to 3725' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing

and squeezed well initially with 5 sacks hulls and 15 sacks gel and followed with 100

Sx. cement from 1025' to 700' then 12 sacks gel from 700' to 220' and followed with

20 Sx. cement from 220' to 160' then 3 sacks gel from 160' to 40' and finally 10 Sx.

cement from 40' to bottom of cellar. Maximum pump-in pressure-350#. FSIP--150#.

Recovered 2600' 4 1/2" casing. (Mudding and cementing operations performed by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 8/1/69

INV. NO. 208-W