

14
KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pan-American Petroleum Corporation,

Complete Address Box #432, Liberal, Kansas.

Lease Name R. L. Zeigler Well No. 1

Location NW-NW-SW Sec. 26 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3719'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Glenn & Smith Pipe Pulling Company,

Address 204 East Sixth Street, Ellinwood, Kansas License No. _____

Operation Completed: Hour 12:15 PM Day 13 Month 11 Year 1969

The above well was plugged as follows:

218'--8 5/8" Surface casing, cement circulated with 125 Sx.

3708'--6" OD Production casing cemented on bottom with 300 Sx. Top perforations from 3698' to 3708'. Casing leak @ 1116' has been squeezed with 110 Sx. cement.

Sanded well back to 3675' and set 5 Sx. cement with dump bailer. Pulled 6" casing

and squeezed well initially with 5 sacks bulls then 30 sacks gel and finally 130 Sx.

cement. Maximum pump-in pressure-500#. Final shut-in pressure-400#. Recovered 700'

6" OD casing. (Mudding and cementing operations by Halliburton Services).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Dickel
Well Plugging Supervisor

DATE 11/17/69
INV. NO. 849-u