

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
1-3-1967  
JAN 3 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Sierra Petroleum Company, Incorporated,

Complete Address: 211 North Broadway, Wichita, Kansas.

Lease Name Holzhauser Well No. 1

Location SW-SW-NW Sec. 26 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3707'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Sun Oil Well Cementing, Incorporated,

Address: Hays, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 4:00PM Day 30 Month 12 Year 1966

The Above well was plugged as follows:

190'--8 5/8" Surface pipe, cement circulated with 140 Sx.  
3705'--5 1/2" Production casing cemented with 100 Sx.  
Well Squeezed from 1169' with Baker plug below and 240 Sx. cement @ 2300#,  
No top of cement indicated. Well temporarily abandoned with rods and  
tubing in hole. In attempting to salvage recovered 72 rods, approximately  
1475' and 35 joints tubing, approximately 1000'. No attempt was made to  
salvage 5 1/2".

Squeezed annulus with 7 Sacks gel followed with 5 Sx. cement FSIP 100#.

Squeezed 5 1/2" with 35 sacks gel and 3 sacks hulls in initial gel followed  
with 80 Sx. cement. Pump-in pressure 550#. FSIP 100#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 1/3/67  
INV. NO. 4540-u