

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 - 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Imperial Oil Company,

Complete Address 780 Fourth National Bank Building, Wichita, Kansas.

Lease Name Biden Well No. 1

Location CE/2-NE-SE Sec. 1 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3936'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 11:30 PM Day 5 Month 10 Year 1969

The above well was plugged as follows:

209'--8 5/8" Surface pipe, cement circulated with 185 Sx.
Top of Dakota section @ 675'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 100 Sx. cement thru
DP from 900' to 575'. Pulled DP to 180' and displaced 20 Sx. cement thru DP from 180'
to 120'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 10/9/69
INV. NO. 620-4

Signed: N. L. Nichols
Well Plugging Supervisor