

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
2-3-1966  
FEB 3 1966  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Shallow Water Refining Company,

Complete Address: 1325 Wichita Plaza, Wichita, Kansas.

Lease Name Holmes Well No. 1

Location CS 1/2-SE-NW Sec. 2 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3813

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase Kansas. License No. 436

Operation Completed: Hour 12:00M Day 30 Month 1 Year 1966

The Above well was plugged as follows:

247'--8 5/8" Surface casing, cement circulated.  
3813'--4 1/2" Production casing cemented with 100 Sx. DV Tool set @ 1816'  
and Chem-Pack circulated to Braden-head. Top perforations @ 3626'.

Pushed plug to 3600', set rock bridge and 5 sacks cement with dump bailer.  
Pulled 4 1/2" to 600', pumped in 19 Sx. gel with no returns. Displaced 20  
Sx. cement thru 4 1/2" @ 600'. Pulled 4 1/2" to 240' and circulated gel thru  
4 1/2" (Used 6 Sx. gel) and displaced 20 Sx. cement thru 4 1/2". Pulled 4 1/2"  
set bridge @ 35' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols  
Well Plugging Supervisor

DATE 2/3/66

INV. NO. 2681-11