
## KANSAS STATE CORPORATION COMMISSION





J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

file No.	County	y:	Graham			
Location: <u>CN를 N를 N트</u>	Sec. 2	<b>qw</b> T	<u> 10 Rge</u>	(E)	(W)	_22
Name of Field:			Total Dep	oth: <u>3812</u>		
I have this date complete	d supervision	of pl	ugging of:			
Lease Name: Brassfie	1d		Well	No. <u>5</u>		
Operator's Full Name:	Leslie Oil	Co				<del></del>
Complete Address:					_	.destablished the
Plugging Contractor	Knight Cas	ing Pu	lling Co			
Address:	Chase, Kan	SAS	Licen	se No. <u>436</u>	· · · · · · · · · · · · · · · · · · ·	
Oll Well Kas Well						
Other well as hereafter I	ndlcated:					
Was any delay in plugging	operations c	aused 1	oy Conserva	Ion Divisi	on Age	n t 🛭
YesNo_x						
If yes how long?	and the second s	Re	ason:	. i		
			,			
						<del></del>
Operation Completed: Hou	r 5PM Day	v <u>16</u>	Month 5	Year_	62	
The above well was plugge	d as follows:					
8 5/8" 228' circulated w	ith cement -	4 <mark>분개 38</mark>	00' with 10	O sax cemen	t.	
Filled with sand to 3800	o', set 4 sax	cement	with dump	bailer, pul	led 12	300
$4\frac{1}{2}$ " to 500', circulated	hole with hea	<b>v</b> y mud	through 4년	" ( 18 sax	Gel),	
displaced 20 sax cement	through 4½" a	t 500'	, heavy mud	to 2001, d	lisplac	:e <b>d</b>
20 sax cement through 42	" at 200', he	avy mu	d to 35', s	et bridge s	ınd	
filled to bottom cellar	with cement.					
Mudding and cementing by	Knight Compa	ny pum	p truck.		·	
			1		•	
		Signe	d: <u>Ales</u> Conserva	Lece,	····	<del></del>
Reviewed: Hard Alel	Q v V I s o r		CONSERVA	IION DAVISI	on Age	AT .

Remarks:

INVOICED

DATE \_ 5/45/62

INV. NO. \_ 5050-W