

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
3-13-1968
MAR 13 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Specter Pipe & Supply, Incorporated,

Complete Address: Box #169, Russell, Kansas.

Lease Name Brassfield Well No. 1

Location NW-NW-NE Sec. 2 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3934'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch Casing Pulling Company,

Address: Great Bend, Kansas. License No. 457

Operation Completed: Hour 12:30PM Day 9 Month 3 Year 1968

The Above well was plugged as follows:

224'--8 5/8" Surface pipe, cement circulated with 150 Sx.

381 1/4'--4 1/2" Production casing cemented with 125 Sx. Well plugged back to 3500.

Push plug to 3450', sand back to 3425' and set 3 Sx. cement with dump bailer. Pull 4 1/2"
casing, and squeeze well using initially 21 sacks gel plug 5 sacks hulls and follow with
100 Sx. cement then 9 sacks gel and follow with 20 Sx. cement then 5 sacks gel and finally
10 Sx. cement to bottom of cellar. (Cementing and mudding operations performed by Allied
Cementing Company, Inc.). Maximum pump-in pressure-750#. Final shut-in pressure-300#

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/13/68
INV. NO. 7411-11

Signed: H. B. Nichols
Well Plugging Supervisor