



Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION 1034511
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 8061
Name: Oil Producers Inc. of Kansas
Address 1: 1710 WATERFRONT PKWY
Address 2: _____
City: WICHITA State: KS Zip: 67206 + 6603
Contact Person: Brian McCoy
Phone: (316) 682-3022
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: E25011.1 Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
KC B Depth to Top: 4464 Bottom: 4672 T.D. _____
Marmaton Depth to Top: 4894 Bottom: 4898 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 15-081-20166-00-01
Spot Description: _____
NE SW SW NE Sec. 25 Twp. 29 S. R. 33 East West
3,173 Feet from North / South Line of Section
2,025 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Haskell
Lease Name: H M DANIELS Well #: 2
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 1/14/2010
Plugging Completed: 1/20/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		PRODUCTION	7	5585	1708

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP @ 4330', RIH w/ tub to 4326' pump 20 sx cmt, pull to 2950' pump 75 sx cmt, free point & cut casing @ 1708', lay down 7", RIH w/ tub to 1638' pmp 50 sx cmt, pull to 710', pump 50 sx cmt, pull to 60' circulate cement to surfac. All cement 60/40 Poz.

RECEIVED
FEB 09 2010

Plugging Contractor License #: 34091 Name: Blackhawk Well Service, LLC
Address 1: 271 LAKE RD Address 2: _____
City: PRATT State: KS Zip: 67124 + _____
Phone: (785) 623-1066
Name of Party Responsible for Plugging Fees: Oil Producers Inc. of Kansas
State of Kansas County, Sedgwick, ss.
Brian J. McCoy Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Submitted Electronically

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

mu