

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 25 Twp. 10 Rge. 2 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW SW

Lease Owner Petroleum, Inc.

Lease Name I. S. White Well No. 1

Office Address Darby Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 4 19 49

Application for plugging filed December 4 19 49

Application for plugging approved December 4 19 49

Plugging commenced 2:P.M. December 4 19 49

Plugging completed 3:20 P. M. December 4 19 49

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elden Petty

Producing formation Depth to top Bottom Total Depth of Well 3795 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Dakota Sand	Water	805'	940'	8 5/8"	324'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Lower plug set at 324' and cemented with 15 sacks of cement, filled hole with mud to 30' below bottom of cellar and set second plug, cemented with 10 sacks of cement.

RECORDED
12-19-1949
DEC 19 1949
STATE OF KANSAS
COUNTY OF HAYS
WICHITA

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Glenn R. Nye Drilling Company, Box 165, Hays, Kansas

STATE OF Kansas COUNTY OF Ellis ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Myl Drilling Co

Ruben Erickson
Hays, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of December 19 49

John L. Spiess

Notary Public.

My commission expires May 9, 1953

22-5133-s 9-48-10M
PLUGGING
FILE SEC 25 T 10 R 24
BOOK PAGE 128 LINE 22

DEC 15 1949

KANSAS

Company: Petroleum, Inc.
 Contractor: Glenn R. Nye Drilling Co.
 Commenced: 11/22/49
 Completed: 12/ 3/49

Farm: White No. 1
 Location: SEC. 25. Twp. 10
 Graham County, Kansas
 Casing Record: 8 5/8" set at 324'

(Figures below indicate bottoms)

surface soilsand	75	shale & lime	2340
sand, shale streak	150	lime & shale	2920
blue shale sand	190	shale lime streaks	2950
shale shells	324	lime shale	3000
shale & sand	550	lime & shale	3020
shale & sand	805	shale & lime	3110
sand	940	lime & shale	3170
shale & sand	965	shale & lime	3195
shale sand	1150	shale lime	3225
sand	1330	lime shale	3255
shale shells red beds	1500	lime shale	3335
shale & shells	1635	lime hard	3370
anhydrite	1675	lime	3400
shale & red bed	1750	lime 346	3460
red bed & shale	1875	lime	3500
sandy shale	1930	lime	3550
shale shells & salt	2180	lime 35	3580
shale & lime	2220	lime hard	3610
lime	2310	lime	3650
lime	2385	lime	3680
lime shale	2455	lime	3710
lime & shale	2470	lime	3720
shale & lime	2570	lime shale streaks	
lime & shale sandy	2645	chert streaks	3750
lime shale	2700	lime - cherty	3777
lime sandy brown	2735	arbuclle	3780
lime	2760	arbuclle - lime	3795 T.D.
lime	2810		


I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

Glenn R. Nye Drilling Company

by Glenn R. Nye

State of Kansas)
) SS
 Ellis County)

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 14 day of Dec, 1949.



John L. Spiess
 Notary Public

My Commission Expires, May 9, 1953

12-15-1949

25.10.210
 108.22