

15-065-01786-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
270 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER None

LEASE NAME White

WELL NUMBER 6

2310 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 25 TWP. 10S RGE. 21 (X) or (W)

COUNTY Graham

Date Well Completed 11/3/61

Plugging Commenced 4/11/90

Plugging Completed 4/11/90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE#(918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by n/a (KCC District Agent's Name).

Is ACO-1 filed? on old form If not, is well log attached? -

Producing Formation Arbuckle Depth to Top 3713 Bottom 3717 T.D. 3717

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil	3713	17	8 5/8	207	-0-
				5 1/2	3713	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Pumped 223 sxs cmt + 200 #'s hulls from TD to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) C. Jan Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

RECEIVED  
STATE CORP  
4-19-1990  
APR 19 1990

SUBSCRIBED AND SWORN TO before me this 17th day of April, 19 90

Judith E. Jernell  
Notary Public



My Commission Expires: 3-29-92

15-065-01786-00-00

KANSAS GEOLOGICAL SOCIETY  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLING BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS


for distribution-see other side

COMPANY Herman Geo. Kaiser, Oil Producer  
 FARM White NO. 6

SEC. 25 T. 10S R. 21W  
 LOC. N/2 NE SW

TOTAL DEPTH 3,717'  
 COMM. 10-22-61 COMP. 11-1-61  
 SHOT OR TREATED  
 CONTRACTOR H-30, Inc.  
 ISSUED

COUNTY Graham  
 KANSAS



CASING  
 20 10  
 15 8 5/8" 207' cem w/125 sx  
 12 6  
 13 5 1/2" 3,713' cem w/125 sx on bottom  
 DV tool @ 1,612' w/375 sx  
 FIGURES INDICATE BOTTOM OF FORMATIONS

ELEVATION 2136 GR  
 2138 DF  
 2141 KB

PRODUCTION

Surface Clay	35
Shale and shells	95
Sand	105
Shale	207
Shale and shells	620
Sand	650
Shale & Shells 3/sand streaks	1040
Sand	1285
Red Bed and Shale	1592
Anhydrite	1639
Shale	2100
Shale and Lime	2265
Lime and Shale	2975
Shale and Lime	3145
Lime and Shale	3428
Lime	3484
K.C. Lime	3516
Lime and Shale	3540
Lime	3580
K.C. Lime	3628
Lime and Shale	3714
Arbuckle	3717
R. T. D.	3717

FILE COPY

Sample Tops

Anhydrite Top	1592	/ 549
Anhydrite Base	1639	/ 502
Heebner	3365	-1224
Toronto	3393	-1252
Lansing	3409	-1268
Base K.C.	3629	-1488
Conglomerate	3693	-1552
Arbuckle	3712	-1571
R. T. D.	3717	-1576

I hereby certify that the above is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Priscilla M. Smert*  
 Priscilla M. Smert

STATE OF KANSAS)  
 ) SS:  
 SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 6th day of November, 1961.

*Geraldine Hays*  
 Geraldine Hays, Notary Public

My Commission Expires:  
 December 3, 1964.

MAR 19 1990  
 3-19-1990  
 CONSERVATION DIVISION  
 Wichita, Kansas