

15-065-01783-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER None

LEASE NAME White

WELL NUMBER 2

660 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 25 TWP. 10S RGE. 21 (N) or (W)

COUNTY Graham

Date Well Completed 9/12/61

Plugging Commenced 1/9/91

Plugging Completed 1/9/91

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE#(918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? on old form If not, Is well log attached? -

Producing Formation Arbuckle Depth to Top 3689 Bottom 3715 T.D. 3715

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil	3689	3715	8 5/8	208	-0-
				5 1/2	3689	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped 360 sxs 65/35 poz w/8% gel + 500# hulls from TD to surface. Pumped 15 sxs cmt down annulus.

Job complete

RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this form.)

2-5-1991
-FEB 5 1991

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

CONSERVATION DIVISION
Wichita, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468



SUBSCRIBED AND SWORN TO before me this 1st day of February, 19 91

Linda M. Woodcock
Notary Public

My Commission Expires: 12-23-93

original to SCC(9/21/61)


COMPANY **Herman Geo. Kaiser**

cc/Ks. Geol. Soc
 SEC. 25 T. 10S R. 21W
 LOC. E/2 SE SW

FARM **White** NO. 2

TOTAL DEPTH **3,698'**
 COMM. **9-1-61** COMP. **9-12-61**
 SHOT OR TREATED
 CONTRACTOR **H-30, Inc.**
 ISSUED

COUNTY **Graham**
 KANSAS



CASING
 20 10 2110 GR
 15 8 5/8" 208' cem w/150 sx ELEVATION 2112 DF
 12 6 2115 KB
 13 5 1/2" 3,689' cem w/125 sx on bottom PRODUCTION
 D.V. tool at 1,602' w/300 sx
FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Clay	30
Shale & Shells	159
Shale	208
Shale & Shells	745
Sand	820
Shale & Shells	1100
Sand	1280
Red Bed & Shale	1473
Red Bed	1572
Anhydrite	1610
Shale	1760
Shale & Shells	2020
Shale	2180
Shale & Lime	2210
Lime & Shale	3140
Shale & Lime	3230
Lime & Shale	3275
Lime w/shale streaks	3316
Lime & Shale	3433
K. C. Lime	3475
Lime & Shale	3510
Lime	3545
K. C. Lime	3597
Lime & Shale	3631
Lime	3671
Lime & Shale	3698
Rotary T. D.	3698

FILE COPY DO NOT REMOVE FROM FILE

Sample Tops

Anhydrite Top	1572	/ 543
Anhydrite Base	1610	/ 505
Heebner	3343	-1228
Toronto	3366	-1251
Lansing	3383	-1268
Kansas City	3607	-1492
Conglomerate	3661	-1546
Arbuckle	3688	-1573
R. T. D.	3698	-1583

I hereby certify that the above and foregoing is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Priscilla M. Ismert
 Priscilla M. Ismert

STATE OF KANSAS)

) SS:
 SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, in and for said county and state this 19th day of September, 1961.

Geraldine Hays
 Geraldine Hays, Notary Public

My Commission Expires:
 December 3, 1964.