

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County, Sec. 25 Twp. 10S Rge. 21 (W)

NORTH

Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Union Texas Petroleum, Inc.
Lease Name Herrold Well No. 5
Office Address Drawer D, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed June 12, 19 53
Application for plugging filed April 28, 19 64
Application for plugging approved April 29, 19 64
Plugging commenced May 28, 19 64
Plugging completed June 10, 19 64
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production November 22, 1960

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation Arbuckle Depth to top 3744' Bottom 3748' Total Depth of Well 3748 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	205	None
				5 1/2	None	1021

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cleaned out cellar. Working pipe. Bridge at 40'. Spudding out bridge.

Sanded to 3730'. Dumped 5 sacks of cement. Working pipe. Shot at 2915'.

Working pipe. Circulating. Spotted 65 bbl. of oil.

Working pipe.

Working pipe. Shot pipe at 2500', 2000', 1500', 1400', 1300', 1200', 1100', 1007'. Pulling pipe.

Pulling pipe. Circulating 18 sacks of mud at 600'. Pumped in 20 sacks of cement at 500'. Pumped 20 sacks of cement at 200'. Build rock bridge at 40'. Capped well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
6-18-1964
JUN 18 1964

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221, Great Bend, Kansas

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Harold Rosenberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Rosenberg
Drawer D, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of June, 19 64

My commission expires Feb. 7, 1966

Esther L. Koch
Notary Public.

15-065-01776-00-00

DRILLER'S LOG

Company: Anderson-Richard Oil Corporation

NW 1/4 NW

Farm Name: Herrold Well No. 5

Sec. 25, Twp. 10S, Rge. 21W,

Total Depth: 3748'

County: Graham,
Kansas

Comm: 6-3-53 Comp: 6-12-53
Contractor: Glenn W. Peel

Elevation:

Casing: 205' 8 5/8" cem.
3742' 5 1/2" cem.

Production:

Figures below indicate bottom of formations:

Surface Clay and Sand	0 -	205
Shale		1100
Sand		1375
Red Bed		1615
Anhydrite		1700
Shale		1935
Shale and Shells		2020
Salt		2050
Lime and Shale		2300
Lime		2570
Sime and Shale		2910
Lime		3050
Lime and Shale		3185
Limo		3748
Total Depth		3748

RECEIVED
STATE CORPORATION COMMISSION
4-30-1964
APR 30 1964
CONSERVATION DIVISION
Wichita, Kansas

This is to certify that the above information is to the best of our knowledge, true and correct.

GLENN W. PEEL

BY: Glenn W. Peel

SUBSCRIBED AND SWORN to before me this 16th day of June, 1953.

My commission expires June 4, 1955

Marion M. H. Hurl
Notary Public