


15-065-02308-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

CORRECTED WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 28 Twp. 10 Rge. (E) 23 (W)
Location as "NE/CNW/SW" or footage from lines 990' N 990' E of SW Corner
Lease Owner Cities Service Oil Company
Lease Name Nemechek Well No. 6
Office Address Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-11 19 57
Application for plugging filed 6-11 19 57
Application for plugging approved 6-11 19 57
Plugging commenced 6-11 19 57
Plugging completed 6-11 19 57
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3885 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	240'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy rotary mud to 600' of surface, set bridging plug @600', ran 25 sacks of cement through drill pipe on top of plug. Filled with heavy mud to 40', dumped 1/2 sack hulls. Mixed 10 sacks of cement and filled to surface.

RECEIVED
STATE CORPORATION COMMISSION
6-28-1957
JUN 28 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lohman-Johnson
Address Evansville, Indiana

STATE OF Kansas COUNTY OF Barton ss.
M. M. Hardin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M M Hardin
P. O. Box 553, Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of June 19 57
March 12, 1959
Notary Public.

PLUGGING
FILE SEC 28 T. 10 R 23W
BOOK PAGE 20 LINE 39

WELL RECORD

WILDCAT.....

DISCOVERY.....

POOL.....

COMPANY Cities Service Oil Co. WELL # 6 FARM Henschel

LOCATION 990' N. and 990' E. of SW Cor., Section 28, Township 10, Range 23 W.

ELEV. 2375 (2373 Or.) CO. Graham STATE Kansas

IP. Dry Hole, P. A. A. June 11, 1957

PERFS.

FRAC. ACID None

T.D. 3885' PBDT. GRAV/GOR.

DRLG. COMM. June 1, 1957 COMP. June 10, 1957 CONTRACTOR Lohmann-Johnson Drlg. Co., Inc.

CASING RECORD:

6-5/8" at 240' with 175 ex. cen.

FORMATION RECORD:

sand and shale	0-200
shale	1010
shale and sand	1660
shale	1895
anhydrite	1929
lime and shale	2090
shale and lime	2505
lime	3318
lime and shale	3402
shale and lime	3512
lime	3885 T.D.

Topeka	3398
Heebner	3614
Dodge	3638
Lansing	3649
Base Kansas City	3682
T.D.	3885

D.S.T. 3791-3823 open 30 minutes, rec. 10' mud; B.H.P. Off in 30 minutes.

D.S.T. 3826-50 open 30 minutes, rec. 6' mud; B.H.P. Off in 30 minutes.

D.S.T. 3854-85 open 30 minutes, rec. 4' mud; B.H.P. Off in 30 minutes.

SLOPE TESTS (Syfo):

500' - 0°
 1000' - 0°
 1500' - 0°
 2000' - 1°
 2500' - 1°
 3000' - 0°
 3500' - 0°

7-7/8" Rotary hole.

RECEIVED
 STATE CORPORATION COMMISSION

6-28-1957
 JUN 28 1957

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING

FILE SEC 28 T. 10 R. 23W

BOOK PAGE 20 LINE 39