


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 28 Twp. 10 Rge. 23 (E) (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines E/2 NE/4  
Lease Owner W. E. Wickizer  
Lease Name Wickizer Well No. B 2  
Office Address WaKeeney, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 4 19 55  
Application for plugging filed February 4 19 55  
Application for plugging approved February 4 19 55  
Plugging commenced February 4 19 55  
Plugging completed February 4 19 55  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 4088 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
	(Set 350' 10 3/4" O.D. 32# csg.)					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug 300', put in some hulls, 20 sax cement, filled on up with mud to 125', set plug, put in some hulls and 10 sax cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to W. E. Wickizer  
Address Box 775, WaKeeney, Kansas

STATE OF Kansas COUNTY OF Trego, ss.  
W. E. Wickizer (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. E. Wickizer*

(Address) *WaKeeney, Kansas* 19 55

SUBSCRIBED AND SWORN to before me this 28th day of February 19 55  
My commission expires 1-12-56



*Stewart M. [Signature]*  
Notary Public.

28-3278-s 4-50-10M  
PLUGGING  
FBI SEC 28 T 10 R 23W  
PAGE 95 LINE 42

RECEIVED  
FEB 28 1955  
CONSERVATION DIVISION  
Wichita

# GOLDEN CAT DRILLING and SERVICING COMPANY

Office Phone 379

Residence Phone 350

P. O. Box 611

To Kansas Well Log Bureau

Well Wickizer B2 NW NW E $\frac{1}{2}$  NE Sec. 28 Tw. 10 R. 23 Co. Graham

Set 350' of 10 3/4" surface pipe

- 0- 70 Surface clay and rock
- 70-350 Sand, shells and shale
- 350-615 Shale
- 615-1285 Shale, sand and shells
- 1285-1625 Shale and sand
- 1625-1892 Red bed
- 1892-1943 Anhydrite
- 1943-2085 Shale and shells
- 2085-2365 Shale and lime
- 2365-2760 Lime and shale
- 2760-3030 Lime and shale
- 3030-3285 Lime and shale
- 3285-3500 Lime and shale
- 3500-3640 Lime and shale
- 3640-3864 Lime
- 3864-3875 Lime
- 3875-4009 Lime and shale
- 4009-4024 Chirt and lime
- 4024-4074 Shale and lime
- 4074-4088 Chirty Conglomerate
- 4088 T D

*J. E. Wickizer*

*Rosetta Jones*  
Witness

**PLUGGING**  
 FILE SEC 28 T 10 R 23 W  
 BOOK PAGE 95 LINE 42

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 FEB 8 1955  
 CONSERVATION DIVISION  
 Wichita, Kansas