

15-065-03204-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER No Record

LEASE NAME Diebolt LKC Unit

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 15-4

1650 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 28 TWP. 10 RGE. 23 (X) or (W)

COUNTY Graham

LEASE OPERATOR Geneva Resources, Inc.

50 California Street, Suite 930

ADDRESS San Francisco, CA 94111

PHONE# (415) 291-9500 OPERATORS LICENSE NO. 30241

Date Well Completed 6/27/55

Character of Well Oil

Plugging Commenced 1/24/91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1/24/91

The plugging proposal was approved on January 24, 1991 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, Is well log attached? Yes

Producing Formation LKC Depth to Top 3530 Bottom 3835 T.D. 3868

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
<u>LKC</u>	<u>Oil</u>	<u>Surface</u>	<u>397</u>	<u>9-5/8"</u>	<u>397'</u>	<u>-0-</u>
		<u>Surface</u>	<u>3867</u>	<u>5-1/2"</u>	<u>3867'</u>	<u>-0-</u>

2-19-1991
FEB 10 1991

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforated at 1100' & 1925'. Ran tbg to 1800' & pumped 55 sx cmt. Pulled tbg up hole to 1000' & pumped 233 sx cmt & circulated. POOH. Hooked up to 5-1/2" csg & pumped 27 sx cmt. Hooked up to 9-5/8" csg & pumped 25 sx cmt to a max press of 300 psi & closed in at 200 psi. Squeezed 5-1/2" csg with 10 sx cmt to a max press of 600 psi and shut in at 350 psi.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address P. O. Box 428, Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Geneva Resources, Inc.

STATE OF California COUNTY OF San Francisco, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 50 California Street, Suite 930
San Francisco, CA 94111

SUBSCRIBED AND SWORN TO before me this 14th day of February, 19 91

[Signature]
Notary Public

Commission Expires: Mar 22, 1991



DIEBOCK LKC Unit #15-4
 15-065-03204-00-00

