

15-065-03203-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER No Record

LEASE NAME Diebolt LKC Unit

WELL NUMBER 15-3

990 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 28 TWP. 10 RGE. 23 (X) or (W)

COUNTY Graham

Date Well Completed 5/31/55

Plugging Commenced 1/23/91

Plugging Completed 1/23/91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Geneva Resources, Inc.

50 California Street, Suite 930

ADDRESS San Francisco, CA 94111

PHONE# (415) 291-9500 OPERATORS LICENSE NO. 30241

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 23, 1991 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached? Yes

Producing Formation LKC Depth to Top 3590 Bottom 3849 T.D. 3900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	391	9-5/8"	391'	-0-
LKC	Oil	Surface	3899	5-1/2"	3899'	-0-

2-19-1991
FEB 10 1991
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. Perforated 1 hole at 1100'. Ran tbg to 1770' & spotted 60 sx of cmt. Pulled up hole to 865' & pumped 135 sx cmt & circulated. POOH. Hooked up to 9-5/8" csg and pumped 40 sx cmt to a max. pressure of 500 psi and closed it in at 500 psi. Hooked up to 5-1/2" csg & squeezed 115 sx cmt to a max pressure of 550 psi. Shut in at 150 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address P. O. Box 428, Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Geneva Resources, Inc.

STATE OF California COUNTY OF San Francisco, ss.


Thomas G. Smith (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Thomas G. Smith
50 California Street, Suite 930
(Address) San Francisco, CA 94111

SUBSCRIBED AND SWORN TO before me this 14th day of February, 19 91

Geraldine Sageser
Notary Public

Commission Expires: Mar. 22, 1991



DIEBOLT LKC UNIT #15-3
15-065-03203-00-00

15-3

HEEBNER

5%

sh
lm
sh
3600
lm
shly
lm
lm
sh
sh
3650
sh
lm
sh
sh
lm
sh
3700
lm
sh
lm
sh
3750
lm
sh
sh
3800
sh
lm

