



KANSAS CORPORATION COMMISSION 1034845
OIL & GAS CONSERVATION DIVISION

Form CP-1
March 2009

This Form must be Typed
Form must be Signed
All blanks must be Filled

WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

OPERATOR: License #: 5056
Name: Holl, F.G., Company L.L.C.
Address 1: 9431 E CENTRAL STE 100
Address 2: _____
City: WICHITA State: KS Zip: 67206 + 2563
Contact Person: Loveness Mpanje
Phone: (316) 684-8481

API No. 15 - 15-047-20630-00-00
If pre 1967, supply original completion date: _____
Spot Description: _____
SW.NE.NE.SE Sec. 8 Twp. 24 S. R. 17 East West
2,242 Feet from North / South Line of Section
419 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Edwards
Lease Name: HAMMEKE Well #: 1-8

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____
Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8.6250 Set at: 248 Cemented with: 225 Sacks
Production Casing Size: 4.50 Set at: 4484 Cemented with: 175 Sacks

List (ALL) Perforations and Bridge Plug Sets:

Attached

Elevation: 2121 (G.L. / K.B.) T.D.: 4485 PBTD: _____ Anhydrite Depth: 1159
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: -
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Hulls, heavy mud, cement and plug according to KCC specifications.

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No
If ACO-1 not filed, explain why:

RECEIVED
JAN 27 2010
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Rob Long
Address: P.O. Box 308 City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 793-0915
Plugging Contractor License #: 31925 Name: Quality Well Service, Inc.
Address 1: 190 US HWY 56 Address 2: _____
City: ELLINWOOD State: KS Zip: 67526 + _____
Phone: (620) 727-3410

Proposed Date of Plugging (if known): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Submitted Electronically

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Form	CP1 - Well Plugging Application
Operator	Holl, F.G., Company L.L.C.
Well Name	HAMMEKE 1-8
Doc ID	1034845

Perforations And Bridge Plug Sets

Perforation Top	Perforation Base	Formation	Bridge Plug Depth
4336	4362	Cherokee Sand	
4376	4388	Mississippi	

RECEIVED
JAN 27 2010
KCC WICHITA

STERLING DRILLING COMPANY
P. O. Box 179
Sterling, Kansas 67579

Well log ----- HAMMERE #1-8
Located: 440' FNL, 440' FEL, SE/4, Section 8-24S-17W,
EDwards County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 26, 1980
COMPLETED: March 4, 1980

TOTAL DEPTH: 4485'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 80 Surface Soil and Sand	Ran 6 joints used 28#, 8 5/8" casing,
80 - 252 Shale	236.60' set at 248' K.B. with 225 sacks
252 - 960 Shale, Sand, Red Bed	60/40 Pozmix with 3% cc. Plug down at
960 - 1159 Red Bed	5:45 PM, 2-26-80, by Howco.
1159 - 1171 Anhydrite	
1171 - 1883 Anhy. - Shale	
1883 - 2100 Shale and Shells	
2100 - 3190 Lime and Shale	
3190 - 3400 Lime	
3400 - 4240 Lime and Shale	
4240 - 4368 Lime	
4368 - 4455 Shale, Lime and Chert	
4455 - 4485 Lime	Ran 108 joints new 10.5#, Range 3, 4 1/2"
	casing. 4474.87' pipe set at 4484' K.B.
	Cemented with 175 sacks 50/50 Pozmix with
	2% gel, 18% salt, 5# gilsonite per sack,
	3/4 of 1% CFR-2 per sack. 110' rotating
	scratchers. Plug down at 11:00 PM,
	3-4-80, by Howco.

RECEIVED
JAN 27 2010
KCC WICHITA

Deviation Surveys: 3/4° at 2348'
3/4° at 4368'



*Mark Parkinson, Governor
Thomas E. Wright, Chairman
Michael C. Moffet, Commissioner
Joseph F. Harkins, Commissioner*

January 27, 2010

Loveness Mpanje
Holl, F.G., Company L.L.C.
9431 E CENTRAL STE 100
WICHITA, KS 67206-2563

Re: Plugging Application
API 15-047-20630-00-00
HAMMEKE 1-8
SE/4 Sec.08-24S-17W
Edwards County, Kansas

Dear Loveness Mpanje:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after July 26, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,
Production Department Supervisor

cc: District 1

(620) 225-8888