

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 52-23
LOCATION NE NE SE
SEC. 15 TWP. 10 RGE. 22

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Andreen
Operator Herman G. Kaiser Address 909 Palace Bldg Tulsa, Okla
Field _____ County Graham
Total Depth 3800 Feet.
Plugging Contractor Ace Pipe Pulling & Globe Cementing Co
Plugging Contractor's License No. 2
Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 259' circulated with cement - 5 1/2" 3800' with 150 sax
cement behind - P. B. to 3770', perforated 3614'

Filled with sand to 3600', set 4 sax cement with dump bailer, pulled
2790' 5 1/2" to 1000', circulated hole with heavy mud at 1000', (Gel Mud),
displaced 20 sax cement through 5 1/2" at 700', heavy mud to 240', displaced
20 sax cement through 5 1/2" at 240', heavy mud to 35', set rock and 10
sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Jesse Petty
District Conservation Agent

10-24-57

RECEIVED
Date
OCT 28 1957
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 15 T. 10 R. 22
BOOK PAGE 52 LINE 23