

15-065-020680000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name D. G. Hansen.
Complete Address: Box # 187, Logan, Kansas.
Lease Name George Gano Well No. C-1
Location NE-NE-SE Sec. 1 Twp. 10 Rge. (E) (W) 24
County Graham Total Depth 4020
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: C & G Drilling Company.
Address: 107 Rule Building, Wichita, Kansas License No.
Operation Completed: Hour 3:00PM Day 17 Month 4 Year 1964

The Above well, was plugged as follows:

188'--8 5/8" Surface pipe, cement circulated with 140 Sx.
Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx
cement thru DP. Heavy mud to 180', set plug with 1/2 sack hulls and dis-
placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack
hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 4/23/64
INV. NO. 9010-u