

15-065-20569-0000

Form CP-3
Rev. 6-4-68

KANSAS

R STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Petroleum, Incorporated.
Complete Address 300 West Douglas, Wichita, Kansas.
Lease Name Gano Well No. B-1
Location NW-NE-SW Sec. 1 Twp. 10 Rge. (E) (W) 24
County Graham Total Depth 3836'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Garvey Drilling Company.
Address Box #1164, Great Bend, Kansas License No.
Operation Completed: Hour 2:30 AM Day 15 Month 10 Year 1972

The above well was plugged as follows:

205'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 925'.

Circulated hole with heavy mud.-- Pulled DP to 1150' and displaced 110-Cu. Ft. cement
thru DP from 1150' to 825'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Dichek*
Well Plugging Supervisor

DATE 10/18/72
INV. NO. 6497-W