

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
11-17-1967
NOV 17 1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Management, Incorporated,

Complete Address 1515 Wichita Plaza, Wichita, Kansas.

Lease Name Walker Well No. 1

Location SE-NE-SW Sec. 20 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3920'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza, Wichita, Kansas. License No.

Operation Completed: Hour 12:15AM Day 15 Month 11 Year 1967

The above well was plugged as follows:

210'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Dakota section from 800' to 990'.

Circulated hole with heavy mud. Pulled DP to 1010' and displaced 100 Sx. cement thru
DP from 1010' to 690'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from 240'
to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 11/19/67
INV. NO. 6696-W