

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SE SE NW

SEC. 20 TWP. 10 RGE. 23 W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Walker 510 Orpheum Bldg.

Operator Walters Drg Co Address Wichita, Kans

Field _____ County Graham

Total Depth 4170 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 186' circulated with cement - 5 1/2" at 3974' with

150 sax cement behind - perforated at 3864.

Filled with sand to 3840', set 4 sax cement with dump bailer,

pulled 2200' 5 1/2" - mudded to 180', set rock and 15 sax cement,

mud to \approx 35', set rock and 10 sax cement to bottom cellar.

Edson Peck
District Conservation Agent

Date 3-19-56

RECEIVED
STATE CORPORATION COMMISSION
3-22-1956
MAR 22 1956
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 20 T. 10 R. 23W
BOOK PAGE 47 LINE 30