

15-065-00017-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Riedel Well No. D-1

Location CSE-SE Sec. 6 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4055

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Barnes & Sons Pipe Pulling Company,

Address: Box #313, Russell, Kansas. License No. 9

Operation Completed: Hour 1:00 PM Day 6 Month 8 Year 1968

The Above well was plugged as follows:

148'--8 5/8" Surface casing, cement circulated with 75 Sx.
3958'--5 1/2" Production casing cemented on bottom with 75 Sx. Well plugged back to
3930'. Top perforations @ 3854'.

Sanded well back to 3825' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well with initially 10 sacks of gel with 5 sacks of hulls in initial
gel, and followed with 100 Sx. cement from 1220' to 900' then 18 sacks gel from 900'
to 160' and followed with 20 Sx. cement from 160' to 100' then 2 sacks gel from 100'
to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in press-
ure-500#. Final shut-in pressure-400#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

Signed: A. S. Nichols

Well Plugging Supervisor

DATE 8/12/68
INV. NO. 8256-U

AUG 12 1968
CONSERVATION DIVISION
Wichita, Kansas