

15-065-03132-0000

Form CP-3  
Rev. 6-26-62

40 KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

DEC 12 1962

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Empire Drg Co

Complete Address: 650 4th Natl Bk Bldg Wichita, Kansas

Lease Name Riedel Well No. E-1

Location CNE SE Sec. 6 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4049

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Barnes & Sons Pipe P, lling

Address: Russell, Kansas License No. 9

Operation Completed: Hour 2PM Day 10 Month 12 Year 62

The Above well was plugged as follows:

8 5/8" 174' circulated with cement - 5 1/2" 4049' with 100 sax cement  
Perf 3979'

Filled with sand to 3950', set 5 sax cement with dump bailer, pulled  
2100' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" ( 30 sax  
Gel), displaced 20 sax cement through 5 1/2" at 550', heavy mud to 160'  
displaced 20 sax cement through 5 1/2" at 160', heavy mud to 35, cement  
to bottom cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 12/12/62

INV. NO. 6211-41