

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NAME Diebolt LKC Unit

WELL NUMBER 7-1
2310 Ft. from S Section Line
4950 Ft. from E Section Line

EASE OPERATOR Manta Petroleum, Inc.
ADDRESS P.O. Box 4491, Englewood, CO 80155
x. 152
PHONE (303) 799-9828, OPERATORS LICENSE NO. 31638

SEC. 21 TWP. 10 RGE. 23 (E) or (W)
COUNTY Graham
Date Well Completed 5/31/54

Character of Well Oil
Oil, Gas, D&A, SWD, Input, Water Supply Well

Plugging Commenced 10/2/97
Plugging Completed 10/2/97

The plugging proposal was approved on October 2, 1997 (date)
by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Lansing-KC Depth to Top 3655' Bottom 3891' T.D. 3897'

Give a brief description of the location, depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LKC 'E'	Oil	3738'	42'	8-5/8"	223'	None
LKC 'E'	Oil	3745'	51'	5-1/2"	3896'	None
LKC 'I'	Oil	3824'	30'			
LKC 'I'	Oil	3840'	49'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug are used, state the character of same and depth placed, from feet to feet each set.
Used 225 sx. 60/40 pozmix - 10% gel - 500# Hulls. squeezed 5-1/2" w/ 210
sx. cement blend with 500# hulls mixed into, max P.S.I. 1000#. Held. Squeezed
8-5/8" W/ 15 sx. cement blend to Max P.S.I. 100#. Held. Plug complete.

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address P.O. Box 31, Russell, KS 67665-0031

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Manta Petroleum, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

DAVID BRADEN (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above-described well, as filed the
the same are true and correct, so help me God.

(Signature) David Braden

(Address) P.O. Box 46, Golden, CO 80402-0046

SUBSCRIBED AND SWORN TO before me this 31ST day of OCTOBER, 19 97

Jeffrey Droegemeier
Notary Public
My Commission Expires DEC 20 1998
JAN 20 1998

My Commission Expires: 09-20-2000

USE ONLY ONE SIDE OF EACH FORM

