

15-005-00886-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County, Sec. 22 Twp. 10S Rge. 23 (X) (W)

Location as "NE/CNW/SW" or footage from lines C NE SE NW

Lease Owner Cooperative Refinery Association

Lease Name Diebolt "A" Well No. 1

Office Address Box 765 Gt. Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed August 28 19 56

Application for plugging filed Verbal permission obtained Aug. 28 19 56

Application for plugging approved Verbal permission obtained 19 56

Plugging commenced August 28 19 56

Plugging completed August 28 19 56

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3900' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	253'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 250'. Dumped 1/2 sx. hulls, 8 5/8" plug and 20 sx. cement through drill pipe. Mud to 40', 1/2 sx. hulls. 8 5/8" plug. Cemented to bottom of cellar.

Name of Plugging Contractor Cooperative Refinery Association Company Rig #5
Address Box 765 Gt. Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Charles Ratzlaff

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles Ratzlaff

Box 765 Gt. Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 29 day of August, 19 56


My commission expires September 2, 1959

Ruth Whove Notary Public.

RECEIVED STATE CORPORATION COMMISSION

AUG 30 1956

CONSERVATION DIVISION
Wichita, Kansas



PLUGGING
FILE SEC. 22 T. 10 R. 23w
BOOK PAGE 94 LINE 26

15-065-00886-0000

DRILLERS LOG

Diebolt "A" #1

Elevation: 2378 R.B.
Casing: 8 5/8 @ 253' w/ 175 sx.
posmix, 2% C.C.

Loc: C-NE SE NW
Sec: 22-10S-23W
Graham County, Kansas
Operator: Cooperative Refinery Ass'n.
Contractor: Company Rig #5

Comm: 8-16-56 Comp: 8-28-56
Total Depth: 3900'

<u>FRom</u>	<u>To</u>	<u>Formation</u>
0	160	Surface hole
160	250	Shale and shells
250	975	Shale
975	1550	Shale and shells
1550	1855	Shale, shells, sand
1855	1965	Red bed, shale and lime
1965	2180	Shale and shells
2180	2420	Shale
2420	2660	Shale and lime
2660	2750	Shale
2750	2980	Shale and lime
2980	3095	Lime
3095	3125	Shale
3125	3810	Shale and lime
3810	3852	Lime
3852	3915	Lime and shale
3915	3900	Lime
3900		T.D.

(STATE OF KANSAS)

(COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the log on the
Diebolt "A" #1 well, located C NE SE NW of Section 22-10S-23W, Graham County, Kansas.

Charles Ritzkeff

Subscribed and sworn to before me this 29 day of August 1956.

Ruth V. Howe



PLUGGING
FILE SEC 22 T 10 R 23W
BOOK PAGE 94 LINE 26

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1956
CONSERVATION DIVISION
Wichita, Kansas