

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County, Sec. 22 Twp. 10S Rge. (E) 23 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C NW NE SE

Lease Owner Cooperative Refinery Association-Ted Gore

Lease Name Conness "A" Well No. 1

Office Address Box 765 Great Bend, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 5-20 19 57

Application for plugging filed 10-3 19 57

Application for plugging approved 10-4 19 57

Plugging commenced 11-14 19 57


Plugging completed 11-21 19 57

Reason for abandonment of well or producing formation

Non commercial production

If a producing well is abandoned, date of last production 10-23 19 57

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Lansing-Kansas City Depth to top Bottom Total Depth of Well 3870 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	262	-0-
				5 1/2"	3869'	3295'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped 50 sacks of mud. Pulled 10 jts. casing. Pumped 10 sx. mid and 20 sx. cement. Drove plug to 240'. Put in 8 gallons of sand, pumped 20 sx. cement. Mudded up to 30'. Pumped 10 sx. of cement. Well complete.

RECEIVED
STATE CORPORATION COMMISSION
NOV 26 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Wilson, Inc.
Address Stafford, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
JOHN H. NATION (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Nation
Box 765 Gt. Bend, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 25 day of November, 19 57

My commission expires Sept. 24. 1960

23-8390-s 6-51-20M

Yvonne Adams

Notary Public.

PLUGGING
FILE SEC 22T 10 R 23a
BOOK PAGE 5 QLINE 39



COPY

DRILLERS LOG

Conness #1

Elevation: 2332' R.B.
Casing: 8 5/8" at 262' w/ 175 sx.

Loc: C NW NE SE
Sec: 22-10S-23W
Graham County, Kansas

5 1/2" at 3869' with 75 sx.

Operator: Cooperative Refinery Ass'n.
Contractor: C.R.A. Company Rig #5

Comm: 5-7-57 Comp: 5-20-57
R.T.D.: 3870'

From	To	Formation
0	262	Clay, post rock, sand
262	550	Shale
550	1620	Shale, sand, shells
1620	1870	Shale, redbed
1870	1910	Anhydrite
1910	2045	Redbed, shale, shells
2045	2305	Shale and shells
2305	3090	Lime and shale
3090	3135	Shale
3135	3675	Shale and lime
3675	3700	Lime
3700	3735	Lime and shale
3735	3818	Lime
3818	3865	Lime and shale
3865	3870	Shale
3870		R.T.D.

RECEIVED
STATE OF KANSAS GEOLOGICAL SURVEY

OCT 4 1957

CONSERVATION DIVISION
TOPEKA, KANSAS

PLUGGING
FILE SEC 22 T 10 R 23W
BOOK PAGE 50 LINE 31