

15-065-02399-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County. Sec. 27 Twp. 10 Rge. (E) 23 (W)

Location as "NE/CNW/SE/SW" or footage from lines NE 1/4 NE 1/4 NE 1/4

Lease Owner Herman Geo, Kaiser, Oil Producer

Lease Name Klenk Well No. 1

Office Address 909 Palace Building, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed Dec 19 1958

Application for plugging filed Dec 19 1958

Application for plugging approved Dec 19 1958


Plugging commenced Dec 19 1958

Plugging completed Dec 19 1958

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius

Producing formation Depth to top Bottom Total Depth of Well 3836 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	211	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with Rotary Mud to 600 ft., set plug and cemented with 20 sacks cement through drill pipe. Mudded hole to 210 ft., set plug and cemented with 20 sacks cement and 1/2 sack Hulls thru drill pipe. Mudded to 40 ft., set plug and cemented with 10 sacks cement and 1/2 sack Hulls to surface.

RECEIVED
STATE CORPORATION COMMISSION

DEC 24 1958

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor H-30, Inc.
Address 709 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick employee of contractor L. C. Sponenberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg

(Address)

SUBSCRIBED AND SWORN to before me this 23 day of December 1958

Feb. 13, 1960

My commission expires

PLUGGING
FILE SEC. 27 T. 10 R. 23W
BOOK PAGE 5 LINE 41



Notary Public.

15-065-02399-0000

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Herman Geo. Kaiser, Oil Producer

SEC. 27 T. 10 R. 23

FARM Klenk

NO. 1

LOC. NE NE NE 1/4

TOTAL DEPTH 3836'

COUNTY Graham

COMM. 12/10/58


COMP. 12/19/58

KANSAS

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED



CASING

20	10	
15	8	211' Cemented with 150 sacks
12	6	
13	5	

2310 K.B.
ELEVATION 2307 D.F.

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand & Gravel	18'
Shale & Shells	1160'
Cement	211'
Chalk, Shale & Shells	765'
Dakota Sand & Clay	1050'
Shale, Shells with Sand Streaks	1160'
Shale & Shells & Red Bed	1350'
Band	1585'
Red Bed and Shale	1847'
Anhydrite	1890'
Shale, Salt and Shells	2180'
Lime & Shale	3597'
Lime	3649'
Lime and Shale	3701'
Lime	3759'
Kansas City Lime	3796'
Lime & Shale	3836'

Formation Tops:

Topeka	3351'
Heebner	3569'
Toronto	3586'
Lansing	3605'
Base Kansas City	3831'

RECEIVED
STATE CORPORATION
DEC 24 1958
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

By *C. L. Spruisky*

STATE OF KANSAS

SS,

COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 23 of Dec. 1958.



Robert Furley
Notary Public

My Commission Expires Feb. 13, 1960

PLUGGING
FILE SEC. 27 T. 10 R. 23W
BOOK PAGE 5 LINE 41