


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Graham County, Sec. 27 Twp. 10 Rge. 23 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines: NE SE NW  
Lease Owner: Dreiling Oil, Inc.  
Lease Name: Geist Well No. 4  
Office Address: Rt. #1 - Box 28, Victoria, KS 67671  
Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole  
Date well completed: 12-15 1975  
Application for plugging filed: 12-15 1975  
Application for plugging approved: 12-15 1975  
Plugging commenced: 12-15 1975  
Plugging completed: 12-15 1975  
Reason for abandonment of well or producing formation: Dry Hole

If a producing well is abandoned, date of last production: 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well: Gilbert Balthazor, Palco, KS  
Producing formation: Depth to top: Bottom: Total Depth of Well: 3,840 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	121'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug was set @ 1200' w/70 sacks cement  
2nd plug was set @ 150' w/20 sacks cement  
3rd plug was set @ 40' w/10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION

JAN 2 1976

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Dreiling Oil, Inc.  
Address: Rt. #1 - Box 28, Victoria, KS 67671

STATE OF KANSAS COUNTY OF ELLIS  
I, Joseph A. Hess, Sec. Treas. of Drig. Contr.

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph A. Hess  
Joseph A. Hess, Hays, KS 67601  
(Address)

IN WITNESS AND SWORN TO before me this 31st day of December, 1975

Cecilia Basgall  
Cecilia Basgall Notary Public.

My commission expires Sept. 13, 1976



15-065-20803-0000

# DREILING OIL, INC.

Victoria, Kansas 67671

## WELL LOG

Company	Dreiling Oil, Inc. Rt. #1 - Box 28 Victoria, KS 67671	Sec. 27	Twp. 10	Rng. 23
Farm	Geist No. 4	Location	NE SE NW	
Total Depth	3,840'	County	Graham	
Comm.	12-9-75	Comp.	12-15-75	Elevation: 2312 K. B.
Contractor	Dreiling Oil, Inc. Rt. #1 - Box 28 Victoria, KS 67671		2309	D. F.
			2307	G. R.

Casing Record  
121' - 8 5/8"

Cement Record  
75 sacks cement

Production:  
D & A

### Figures Indicate Bottom of Formations

0'	30'	Top Soil-Sand
30'	1375'	Shale
1375'	1590'	Sand
1590'	1844'	Shale
1844'	1886'	Anhydrite
1886'	2415'	Shale
2415'	2739'	Shale & Lime
2739'	3160'	Shale
3160'	3477'	Shale & Lime
3477'	3840'	Lime
3840'		

RECEIVED  
STATE CORPORATION COMMISSION  
T.D.

JAN 2 1976

CONSERVATION DIVISION  
Wichita, Kansas


STATE OF KANSAS)  
COUNTY OF ELLIS)

I, Joseph A. Hess, Secretary Treasurer of Dreiling Oil, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Geist #4.

*Joseph A. Hess*  
Joseph A. Hess

Subscribed and sworn to before me this 31st day of December, 1975.

*Cecilia Basgall*  
Cecilia Basgall Notary Public



My commission expires: September 13, 1976.