

15-065-22474-0000

7-27-88

065-22,474

6 080115

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

SE NE NW SW, SEC. 2, T 10 S, R 22 W/E

4290 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9705

Lease Name Germany Well # 1

Operator: Mid American Hydrocarbon, Inc

County Graham 124.48

Name & Address 114 E. Ave., N., Box 723

Well Total Depth 3830 feet

Lyons, Kansas 67554

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 200'

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Operations License Number 8241

Address Russell, Kansas 67665

Company to plug at: Hour: am Day: 28 Month: 27 Year: 19 88

Plugging proposal received from

(company name) (phone)

were: Order 215 sx 60/40 poz-mix, 6% gel, 3% cal cl, 1sk flo-cel and 8 5/8" plug.
Spot with drill pipe with no less than 36 vis. mud between all plugs, with good
circulation and no fluid loss.

RECEIVED
STATE CORPORATION COMMISSION
6-23-1988
AUG 23 1988

Plugging Proposal Received by Bruce D. Basye (TECHNICIAN)

Plugging Operations Spons. S. by Agent?: All Part None XX

Operations Spons. S. by Agent?: Hour: 7:00am Day: 27 Month: 07 Year: 1988

ACTUAL PLUGGING REPORT 1st plug @ 1820' w/ 25 sx.

2nd plug @ 975' w/ 100 sx, 1 sk flo-cel

3rd plug @ 250' w/ 40 sx.

4th plug @ 40' w/ 10 sx.

15 sx in rat hole, 15 sx in mousehole.

Remarks: Cemented by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-24-88

Signed Bruce D. Basye (TECHNICIAN) Bruce D. Basye

INVOICE NO. 21898