

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21206-00-00
Spot: CSWNENE Sec/Twnshp/Rge: 2-10S-22W
990 feet from N Section Line, 990 feet from E Section Line
Lease/Unit Name: BRASSFIELD Well Number: 1
County: GRAHAM Total Vertical Depth: 3989 feet

Operator License No.: 3194
Op Name: TRI UNITED, INC
Address: 950 270TH AVE
HAYS, KS 67601

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 238 170 sx cmt \$129.64
Production: Size 4.5 feet: 3915 200 sx cmt
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/09/2001 10:00 AM
Plug Co. License No.: 3194 Plug Co. Name: TRI UNITED, INC
Proposal Rcvd. from: EUGENE LEIKER Company: TRI UNITED, INC Phone: (785) 628-3670

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/09/2001 12:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

8 5/8" S.P. - squeezed 50 sxs cement with 100# hulls down annulus.
Max. P.S.I. 100#. S.I.P. 100#.
4 1/2" casing - RIH with tubing to 1800' - spotted 100 sxs cement with 300# hulls to circulate at surface.
POOH with tubing.
Squeezed 4 1/2" casing with 30 sxs cement.
Max. P.S.I. 800#. S.I.P. 500#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Dennis L. Hamel
(TECHNICIAN)

RECEIVED

INVOICED

Form CP-2/3

OCT 16 2001

DATE 10-16-01

KCC WICHITA

INV. NO. 2002060813


OCT 10 2001

F & J OIL COMPANY, INC. #1 BRASSFIELD 2-10-22W
 BOX 735 EL DORADO, KS. 67042 SW NE NE

CONTR JOHN O. FARMER, INC. CTY GRAHAM

GEOL ROGER WELTY FIELD BRASSFIELD

E 2322 KB CM 2/20/80 CARD ISSUED 7/4/80 IP P 10 B0 & 20 BWPD
 LKC 3722-25



API 15-065-21,206

SMP	TOPS	DEPTH	DATUM
ANH	1785	+1046	
TOR	3531	-1209	
LANS	3534	-1212	
BKC	3777	-1455	
MARM	3843	-1521	
ARB	3917	-1595	
LTD	3917	-1595	

8-5/8" 238/170sx, 4 1/2" 3915
 DST (1) 3574-3615 (LKC)/30-30-30-30,
 1' FO, 540' SOCMW, SIP 672-661#,
 FP 65-163/185-272#, HP 1917-1907#,
 BHT 106°
 DST (2) 3664-3700 (LKC)/45-45-45-45,
 10' SOCM, (10% O), 55' M, (2% O),
 SIP 1075-1044#, FP 54-65/65-76#,
 HP 1981-1971#, BHT 017°
 DST (3) 3695-3758 (LKC)/30-30-30-30,
 140' SO&GCM (10% O), 120' O&GCM
 (30% O), 180' HO&GCM (40% O), TR
 W (3% O), SIP 360-349#, FP 65-174/
 185-240#, HP 1949-1939#.
 MICT - CO PF (LKC K) 4/3722-25, AC
 2000 (28%), POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS