

4-060559

8-13

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,745

C NW NW /4 SEC. 02, 10 S, 22 W
4620 feet from S section line
4620 feet from E section line

Operator license# 5030

Lease T. Brassfield well # 1

Operator: Vess Oil Corporation

County Graham

Address: 8100 E. 22nd. St.
N. Building #300
Wichita, Kansas 67226

Well total depth 3810 feet ^{123.83}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 216 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: P.O. Box 819 - Russell, Kansas 67665

Company to plug at: Hour: 1:30A.M. Day: 13 Month: August Year: 94

Plugging proposal received from: Jack Fox

Company: Emphasis Oil Operations Phone: 913-483-3518

Were: Oeder 190 sxs. 60/40 posmix - 6% gel with 1/4# flocele per. sx.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 1:30A.M., Day: 13, Month: August, Year: 94

Actual plugging report:

1st. plug @ 1860' w/25 sxs. - Anhydrite 1849' - 1886'.

2nd. plug @ 1035' w/100 sxs. - Dakota 729' - 1029'.

3rd. plug @ 270' w/40 sxs. - Surface pipe to 216'.

4th. plug @ 40' w/10 sxs.

Rathole with 15 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO STATE

Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO

Plugged through TUBING , CASING . Elevation: 2354 GL

I did[] did not[X] observe the plugging.

INVOICED

DATE

9-6-94

BY

41112

[Signature]

(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
8-23-1994
AUG 23 1994
CONSERVATION DIVISION
WICHITA, KANSAS